

NOTES:

- CROSS SECTION MAY BE ADJUSTED DEPENDING ON EXISTING CONSTRAINTS AS APPROVED BY THE CITY ENGINEER.
- SLOPE TRAIL AS NECESSARY TO AVOID PONDING. PROVIDE DRAINAGE IMPROVEMENTS ALONG TRAIL AS REQUIRED TO CONVEY POSSIBLE STORM FLOWS.
- 3. ALL TREES, SHRUBS, AND OTHER VEGETATION SHALL BE REMOVED FROM THE CLEAR ZONE.
- 4. ALL WEEDS SHALL BE SPRAYED & KILLED w/ ROUNDUP OR APPROVED EQUIVALENT ONE WEEK BEFORE ANY WORK MAY BE PERFORMED, & WITHIN 3 WEEKS OF THE PLACEMENT OF UNTREATED BASE COURSE.

16

| STANDARD # | MJV | CHECKED BY:
BT | SCALE:
N.T.S.
DATE:
2/14/2018 | TRAIL SECTION DETAIL

