



- NOTES:**
1. PAVEMENT CUTS SHALL BE A MINIMUM OF 3' X 3' AND ALSO BE MADE 12 INCHES OUTSIDE THE EDGE OF TRENCH FOR TRENCHES DEEPER THAN 4 FEET.
 2. BEDDING MATERIAL SHALL EXTEND A MINIMUM OF 3" BELOW THE PIPE. FOR CONCRETE PIPE LARGER THAN 24" I.D. A MINIMUM OF 6" OF BEDDING MATERIAL SHALL BE PLACED BELOW THE PIPE.
 3. ASPHALT SHALL BE CUT TO THE SPECIFIED WIDTH DURING PIPELINE CONSTRUCTION AND SUBSURFACE RESTORATION. THE FINAL SAW-CUT SHALL BE AN ADDITIONAL 12" WIDER THAN THE EXISTING TRENCH ON EACH SIDE, REMOVING THE ASPHALT AND PROCEEDING WITH THE REMAINDER OF THE RESTORATION.

6	DRAWN BY: BDS
	CHECKED BY: BT
	SCALE: N.T.S.
	DATE: 2/14/2018
	STANDARD #

CONSTRUCTION STANDARDS

SEWER AND WATER PIPE TRENCH/ ASPHALT PATCH DETAIL

<p>680 S. Woodland Hills Dr. Woodland Hills, UT 84653 P Phone: 801-423-1962 F ax: 801-423-3501 www.woodlandhills.org</p>	 <p>CITY OF WOODLAND HILLS</p>
--	--